



City of Tacoma

ENVIRONMENTAL SERVICES DEPARTMENT

ADDENDUM NO.1

DATE: March 27, 2023

REVISIONS TO:

Request for Bids Specification No. ES23-0026F

CENTRAL WASTEWATER TREATMENT PLANT SECONDARY CLARIFIER #5 RESTORATION

NOTICE TO ALL BIDDERS:

This addendum is issued to clarify, revise, add to or delete from, the original specification documents for the above project. This addendum, as integrated with the original specification documents, shall form the specification documents. The noted revisions shall take precedence over previously issued specification documents and shall become part of this contract.

REVISIONS TO THE SUBMITTAL DEADLINE:

The submittal deadline has been changed to 11:00 a.m., Pacific Time, Tuesday, April 4, 2023.

REVISIONS TO THE PROPOSAL PAGES:

Change No. 1 – Revision to Bid Proposal Sheet

Add the following to Bid Item #2:

#2A. Epoxy Crack Injection Estimate Quantity: 300 LF Unit Price: Linear Feet

The attached Proposal has been revised to reflect the above changes and is labeled "Addendum No. 1." The bidder shall insert the revised proposal into the Bid Submittal Package and use the revised proposal in lieu of the original.

REVISIONS TO THE SPECIFICATIONS:

Change No. 1 – Revision to Section 01 11 00.1.02.B

Add the following new section:

Bid item 2A: Epoxy Crack Injection,

Work includes but is not limited to, providing all labor, certified supervision, materials, tools, and equipment required to execute epoxy injection to concrete substrate cracks as described in accordance with these Specifications and shown in the Plans or as established by the Engineer. Payment shall be based per Linear Feet.



City of Tacoma

REVISIONS TO THE PLANS:

Change No. 1 – Revision to Detail A – Detail A, sheet 13 of 13

Delete note referencing anchor and deflector plate size and replace with the following:

Contractor shall install new 1/4" 316 SST anchors and new 3/16"x 4"x 4" 316 SST Deflector plates on All New Cored Holes.

Change No. 2 – Revision to Sheet 9 – Detail B, sheet 9 of 13

Delete Note referencing radius distance 58'-9" and replace with the following:

Radius dimension from Baffle plate to center of tank is 57' Contractor must field verify before fabrication.

Change No. 3 – Revision to Sheet 9 – Detail 2, sheet 9 of 13

Delete Note referencing radius distance 58'-9" and replace with the following:

Radius dimension from Baffle plate to center of tank is 57', Contractor shall field verify before fabrication.

NOTE: Acknowledge receipt of this addendum by initialing the corresponding space as indicated on the proposal page. Vendors who have already submitted their bid/proposal may contact the Purchasing Division at 253-502-8468 and request return of their bid/proposal for acknowledgment and re-submittal. Or, a letter acknowledging receipt of this addendum may be submitted in an envelope marked Request for Bids Specification No. ES23-0026F Addendum No. 1. The City reserves the right to reject any and all bids, including, in certain circumstances, for failure to appropriately acknowledge this addendum.

Addendum No.1

B I D P R O P O S A L

SPECIFICATION NO. ES23-0026F

CENTRAL TREATMENT PLANT

SECONDARY CLARIFIER #5

RESTORATION

The undersigned hereby certifies that he/she has examined the location and construction details of work as outlined on the Plans and Specifications for Project No. **ENV-04015-20** and has read and thoroughly understands the Plans and Specifications and contract governing the work embraced in this improvement and the method by which payment will be made for said work, and hereby proposes to undertake and complete the work embraced in this improvement in accordance with said Plans, Specifications and contract and at the following schedule of rates and prices:

- NOTE: 1. All extensions and total amount of bid should be shown. Show unit prices in figures only.
2. Additional information pertaining to the description of the below bid items can be found in Section 01 11 00 Summary of Work.

<u>ITEM NO.</u>	<u>ITEM DESCRIPTION</u>	<u>ESTIMATED QUANTITY</u>	<u>UNIT PRICE</u>	<u>TOTAL AMOUNT</u>
1	Demolition, removal of existing 2" thick grout layer and baffle skirts for Secondary Clarifier.	Lump Sum	Lump Sum	\$_____
2.	Secondary Clarifier restoration, patching, repair of existing substrate.	Lump Sum	Lump Sum	\$_____
2A.	Epoxy Crack Injection	300 LF	Linear Feet	\$_____
3.	Installation of new 2" thick new Secondary Clarifier Topping Slab Grout layer.	Lump Sum	Lump Sum	\$_____
4.	Concrete and Ferrous Surfaces Preparation and Coating.	Lump Sum	Lump Sum	\$_____
5.	Procure and Installation of New 1/4" Thick Steel Baffle Skirts, 1/2" SST splash plate, and Brush System.	Lump Sum	Lump Sum	\$_____
6.	Mechanical and Electrical appurtenance replacement on all six (6) secondary clarifiers.	Lump Sum	Lump Sum	\$_____
Base Bid (Subtotal Item Nos. 1-6)				\$_____
10.3 % Sales Tax (Item Nos. 1-6)				\$_____
GRAND TOTAL (Base Bid, Sales Tax)				\$_____